


# SKETCH REPORT

### **Residential Re-Roof**

Property address 3470 Compton Dr Columbus, OH 43219



### SKETCH REPORT | PITCH DIAGRAM




**Residential Re-Roof** 

August 13, 2019

**Property address** 3470 Compton Dr Columbus, OH 43219

# SKETCH REPORT | MEASUREMENTS DIAGRAM



**Residential Re-Roof** 

August 13, 2019

**Property address** 3470 Compton Dr Columbus, OH 43219

### SKETCH REPORT | MEASUREMENTS

#### Waste calculation

SUGGESTED WASTE

	Actual	+5%	+10%	+10.75%	+15%	+20%
Squares	23.24	24.4	25.56	25.74	26.73	27.89
Area	2,324 ft. <sup>2</sup>	2,440 ft. <sup>2</sup>	2,556 ft. <sup>2</sup>	2,574 ft. <sup>2</sup>	2,673 ft. <sup>2</sup>	2,789 ft. <sup>2</sup>

<sup>\*</sup>The suggested waste percentage only applies when installing standard architectural shingles and a closed, single-cut valley system. The calculation includes 2.3 SF per LF of valley, 0.7 SF per LF of hip, 0.25 SF per LF of rake, and 0.25 SF per LF of step. In addition, a 5% handling waste is included. NOTE: This percentage accounts for field shingle waste only. Ridge cap, hip cap, and starter bundles should be accounted for separately.

#### **Line measurements**

Eaves	119 ft.	
Rakes	118 ft.	
Ridges	79 ft.	
Hips	9 ft.	
Valleys	39 ft.	
Step	21 ft.	
Wall	1 ft.	
Pitch change	O ft.	

#### **Category measurements**

Ice & water shield	0 ft.
Ridge vent	0 ft.
Rake edge	0 ft.
Eave edge	0 ft.
Step flashing	0 ft.
Apron flashing	0 ft.
Gutters	0 ft.
Gutter toppers	0 ft.
Down spouts	0 ft.

#### **Pitch measurements**

**5/12** 23.24 sqs.


**Residential Re-Roof** 

August 13, 2019

**Property address** 3470 Compton Dr

Columbus, OH 43219

### SKETCH REPORT | AREA DIAGRAM



**Residential Re-Roof** 

August 13, 2019

**Property address** 3470 Compton Dr Columbus, OH 43219

### SKETCH REPORT | ASSESSMENT



**Residential Re-Roof** 

August 13, 2019

**Property address** 3470 Compton Dr Columbus, OH 43219

## SKETCH REPORT | ASSESSMENT

1.



Hail Damage



You can upload photos and annotate them!

2.



Replace 3"- 5" Type-B Furnace Vent Cap You can also store notes on pins without including photos.

3.



Install (1"- 3") Rubber Plumbing Boot

Residential Re-Roof August 13, 2019 **Property address** 3470 Compton Dr Columbus, OH 43219